

basic education

Department:
Basic Education
REPUBLIC OF SOUTH AFRICA

NATIONAL SENIOR CERTIFICATE

GRADE 12

CIVIL TECHNOLOGY

EXEMPLAR 2014

MEMORANDUM

MARKS: 200

This memorandum consists of 15 pages.

QUESTION 1: CONSTRUCTION, SAFETY AND MATERIAL

1.1	1.1.1	 A Direction of escape route √ Emergency escape B Face protection √ C Fire and open flames prohibited √ No lighting of matches (Any ONE of the above or any other acceptable answer) 	(3)
	1.1.2	 Workshop, hotels, hospital J Grinding, working with a jackhammers J Spraying toxic chemicals Protection against flying debris Where flammable gasses and liquids are stored J Outside stores for petrol and oils 	
1.2	1.2.1	(Any ONE of the above or any other acceptable answer) Segregation is the separation of aggregates, such as stone, sand and cement due to transporting of fresh concrete on rough roads. ✓	(3)
		(Or any other acceptable answer)	(1)
	1.2.2	A slump is the distance between the top of the concrete and the underside of the straight edge which rests across the top of the mould after a slump test is conducted. I	
		(Or any other acceptable answer)	(1)
	1.2.3	Compaction is the process of removing trapped air in concrete to make the concrete more dense and strong. \checkmark	
		(Or any other acceptable answer)	(1)
1.3	1.3.1	 Bags of cement should be stored in a dry place. √ It must be stored on wooden beams. √ It must be covered with plastic sheets or steel plates. It must not come into contact with water. 	
		(Any TWO of the above or other acceptable answer)	(2)
	1.3.2	Cement causes skin disorders and chemical burns. J	(1)
	1.3.3	Provide them with a dust mask. J	(1)

Tools should always be in good working order. √

- Ensure that all cutting edges of tools are sharp. **J**
- Carry tools that have sharp blades with the blade facing the ground so that others may not be injured. ✓
- Work with sharp parts of tools away from your body.
- Use tools only for purposes for which they were designed.
- Service and maintain tools regularly.
- Work only in well-lit areas.
- Report any defective tools immediately.
- Follow the safety rules of the manufacturer of the tools.

(Any THREE of the above or other acceptable answer)


(3)

- 1.5 Use latex gloves.
 - Treat wound with disinfectant. J
 - Apply direct pressure on the wound with a pad. J
 - Cover wound with sterile dressings.
 - Do not touch blood with bare hands.
 - Dress with bandages.

(Any TWO of the above or other acceptable answer)

(2)

1.6



(4)

- 1.7 Bricks ✓
 - Tiles √
 - Concrete

(Any TWO of the above or other acceptable answer)

(2)

1.8 150 mm to 170 mm ✓

(1)

1.9 A – Frame head $\sqrt{ }$

B – Rebate/Horn √

C - Window stile/Casement stile /

D – Glazing bar ✓

E – Bottom rail of casement ✓

(5)

[30]

Civil Technology 4 DBE/2014 NSC – Grade 12 Exemplar – Memorandum

QUESTION 2: ADVANCED CONSTRUCTION AND EQUIPMENT

2.1 2.1.1 A – Preformed/precast concrete pile. *J* (1)

B – Cable. J (1)

C – Sledgehammer/drop hammer. (1)

2.1.2 • Unstable, soft soil or loose soil

Non-adhesive soil √

• Where there is ground movement

Soil that is constantly wet

(Any TWO of the above or other acceptable answer)

(2)

2.2 **CRITERIA** STRIP FOUNDATION PILE FOUNDATION Advantage Cheap/quicker/no Solution for foundations on special machines unstable soil/less chance of required. ✓ foundation collapsing \(\int \) Trenches are dug by Pile holes are drilled into the Equipment used workers using shovels for digging of earth with an auger type bit foundation and picks or mechanical or drill. ✓ diggers. \(\brace{1}{3} \) Mechanical driven auger (4) drill 1

2.3 Setting out the template to make the truss./Testing members for squareness. *J*(Or any other acceptable answer) (1)

2.3.2 Heavy nailwork/extract of nails/Hammering in of nails.

(Or any other acceptable answer) (1)

2.4 A – Round bar/mild steel rod *J* (1)

B – Ribbed bar/high tensile steel **/** (1)

2.5 A **rough arch** is built using standard, common bricks where wedge-shaped mortar joints form the shape of the arch. These types of arches will be completely plastered. **J**

Gauged arches are built with face bricks or voussoirs that are tapered on both sides before they are used in the arch. These types of arches will not be plastered. The mortar joints are jointed J

(Or any other acceptable answer) (2)

2.6 2.6.1 C – Apply gypsum plaster to joints first. ✓

 $\mathsf{E}-\mathsf{Apply}$ self-adhesive gauze to cover equal area on either side of the joints. J

A – Apply a second layer of gypsum plaster on top of the self-adhesive gauze. \boldsymbol{J}

D – Apply thin final coat of gypsum plaster and let dry. J

B – When the joint is dry, sand lightly with fine sandpaper. $\sqrt{}$ (5)

DBE/2014 Civil Technology NSC - Grade 12 Exemplar - Memorandum 2.6.2 Dry wall construction is quicker to build. *I* It is cheaper to build. \(\begin{align*} \lambda \\ \lambda \end{align*} It is lighter than brick or block walls. (Any TWO of the above or other acceptable answer) (2) 2.7 Humidity negatively influences the safety of the entire structure. The health of occupants can be negatively affected. \checkmark The furniture can be affected. \checkmark Paintwork can be affected. (Any THREE of the above or other acceptable answer) (3) 2.8 The right concrete mix ratio not used. ✓ The right curing process not followed. $\sqrt{\ }$ If the main bars and stirrups is not the right diameter. \boldsymbol{J} The stirrups/binders not used correctly. Insufficient reinforcement Binders not spaced correctly (Any THREE of the above or other acceptable answer) (3) 2.9 2.9.1 A – Steel mat/Reinforcing mesh/Reinforcing bars ✓ B – Reinforcement in ribs ✓ C – Hollow-core concrete blocks ✓ D – Pre-stressed concrete ribs ✓ E – Bearer joist ✓ (6) F – Props/post/pole J 2.9.2 E – To make sure that the ribs and blocks are level. To prevent the ribs from bending along the span. $\sqrt{}$ (1) F – To keep the joist and bearer propped up. It also prevents any bouncing of the material J (1) (Or any other acceptable answer) 2.9.3 Rib and block construction (1) 2.9.4 Units are cast in exact shapes and exposed to thorough curing and testing. ✓ Inflatable foam rubber, plastic-centred rib moulds are used during shaping process. J This reduces cost and weight. J Lightweight components require less support during construction. ✓ The ceiling is ready to be plastered. Reinforcement can be inserted during construction. High-pressure pumps and vibrators can be used to force

Copyright reserved Please turn over

concrete into the openings and passages

Materials are cost-effective

3.1

(3) **[40]**

- Excellent structural integrity.
- Easy set-up procedures save time.
- No skilled labour is needed.
- Improved sound and temperature insulation.
- Require minimal formwork.

ADVANTAGES

a) Can be used for cold and hot

- Quality plastered soffits (no joints).
- Units reduce the volume of concrete needed.

(Any FOUR of the above or other acceptable answer)


a) Heavy. √

DISADVANTAGES

QUESTION 3: CIVIL SERVICES

	wa	ter.√		
	b) Du	rable √ .	b) Not easy to work with, screw	
			tread must be cut on both sides√.	
	c) Lov	w maintenance. √	c) Can rust if acid content of soil is	
			high and placed under water. ✓	
	(Or any	other acceptable answer)		(6)
3.2	3.2.1	Manhole at a junction. J		(1)
	3.2.2	From B and C towards A. J		(1)
	3.2.3	It is open so that a rod can be to get rid of blockages. √	be used to enter the sewer line in order	
		NOTE: It can also be closed	if a junction access is used.	(1)
	3.2.4	Where branch pipes connect	to main sewer pipe.	(1)
	3.2.5	25 metres √		(1)
	3.2.6	Rodding eye √		(1)
3.3	3.3.1	IL J		(1)
	3.3.2	VP √		(1)
	3.3.3	DB √		(1)

3.4



Line type	1	
Connection angle	1	
Pipe material/gradient	3	
Rodding eye	1	
Gully	1	
Vent pipe	1	
Manhole	1	
Inspection eye	2	
Hand washbasin	1	
Water closet	1	
Sink	1	
Bath	1	
TOTAL	15	

QUESTION 4: QUANTITIES AND CALCULATIONS AND JOINING

4.1

4.1.1

Α	В	С	D
Multiply	Dimension per Item	Answer	Description
			Total area of wall
1/	6 √		
	<u>2,7</u> √		
		16,2 m² √	(3)

4.1.2

			Area of Window 1
1/	1,2 √		
	<u>1,5</u> √		
		1,8 m² √	(3)

4.1.3

			Area of Door 1
1/	2,0 √		
	<u>0,9</u> √		
		1,8 m² √	(3)

4.1.4

			Total area of wall, excluding the window and door
1/	16,2 √		
	-3,6 √		
		12,6 m² √	(3)

4.1.5

			Total number of bricks, including 5 for wastage	%
1/	12,6			
	110			
		1 386 √	1 386 bricks	
			+ 5% of 1 386 = 69,3 or 70 bricks ✓	
			1 386 + 70 = 1 456 bricks ✓	(3)

4.2 4.2.1 Capillary joint - solder is used to keep the pipes from moving apart. √ Compression joint - ferrule and cup nut will keep the pipes from (2) moving apart. \(\brace{1}{3} \) 4.2.2 Monkey wrench. ✓ (2) Adjustable spanner (Shifting)/open-end spanner correct size. \(\int \) 4.3 Hammer fix nylon anchor. ✓ Universal plug. ✓ (2)Wall plug. ✓ 4.4 The cube must first be cleaned. \(\square\$ Apply a layer of mould oil on the inside of the cube. \checkmark The concrete should be placed in the form in layers of 50 mm. J Each layer must be tamped 38-45 times with a tamping rod to get rid of all the air bubbles. \(\bigvel{I} \) The last layer should be higher than the top of the cube form and is levelled with a steel trowel. (Any FOUR of the above or other acceptable answer) (4) 4.5 A slump test is carried out to determine the consistency and workability of the different batches of freshly mixed concrete for one single placing JTo determine whether the ratio between water, sand and stone is correct (1) (Any one of the above) 4.6 A – Used as beams in the building industry. ✓ B – Carports, steel roof trusses. ✓ (3) C – Manufacturing of steel roof trusses, columns, pillars and bridges. 4.7 You can galvanise it. ✓ It could be plated with zinc, chrome or brass. It can be painted.

Copyright reserved Please turn over

(Any one of the above)

(1)

[30]

QUESTION 5: APPLIED MECHANICS

5.1 **ANSWER SHEET 5.1**

Area of figure A1 = sxs(Square) $= 60 \times 60$ $= 3600 \text{ mm}^2$

Area of figure A2 $= \frac{1}{2} b x h$ $= \frac{1}{2} \times 60 \times 15$ (Triangle) $= 30 \times 15$ $= 450 \text{ mm}^2$

Total Area $= 3600 \text{ mm}^2 + 450 \text{ mm}^2$ $= 4 050 \text{ mm}^2$

Position of centroid from B on Y-axis = $(A1 \times d) + (A2 \times d)$ Total area J $= (3600 \times 45) + (450 \times 10)$ 4 050 mm² J $= 162\,000 + 4\,500\,J$ 4 050 mm² = 166 500 J 4 050 mm²


= 41,11 J mm JTake moments around B on Y-axis


J $4\ 050\ \text{mm}^2\ \text{x}\ \text{X} = (3\ 600\ \text{x}\ 45) + (450\ \text{x}\ 10)$ 4 050 mm² x X = 162 000 + 4 500

 $X = 166 500 \text{ mm}^2 \text{J}$ 4 050 mm² J = 41,11 J mm J

PART	AREA (A)	X	AREA OF X (Ax)
Square	3 600 mm² /	$\underline{S} = \underline{60} = 30 + 15 = 45 $	162 500 mm ²
		$\overline{2}$ $\overline{2}$	
Triangle	450 √	<u>h</u> = <u>15</u> = 5 + 5 = 10 √	4 500 mm ²
		$\overline{3}$ $\overline{3}$	
Σ	4 050 mm ² J		166 500 mm² √

 ΣAX 166 500 mm³ √ 4 050 mm² (9)41,11 J mm J





b е d (4)

5.2.2

MEMBER	NATURE	MAGNITUDE OF FORCE
AE	Strut ✓	4 kN √
BE		
CF	Strut	7 kN √
DF	Tie √	6,1 kN /
EF	Strut 1	7 kN

(6)

(5)

5.3.1 SFa (0 metres from A) = left reaction force

= 20 N J

SFb (2 metres from A) = left reaction force – point load b

= 20 N - 0 N

= 20 N J

SFc (4 metres from A) = left reaction force – point load b – point load c

= 20 N - 0 N - 0 N

= 20 N J

SFe (6 metres from A) = left reaction force – point load b – point load c –

uniformly distributed load d – point load e

= 20 N - 0 N - 0 N - 40 - 20 N

= -40 N J


SFf (6 metres from A) = left reaction force – point load b – point load c –

uniformly distributed load d - point load e +

right reaction force

= 20 N - 0 N - 0 N - 40 - 20 N + 40


= 0 N J



14 DBE/2014

QUESTION 6: GRAPHIC COMMUNICATION

ANSWER SHEET 6.1



QUESTION	ASPECT	MARKS	
6.1.1	External walls	4	
	Internal walls	3	
6.1.2	Windows	4	
	Doors	4	
6.1.3	Built-in cupboard	1	
	Water closet	1	
	Shower	1	
	Washbasin	1	
	Sink	1	
6.1.4	Hipped roof	5	
6.1.5	Dimension	1	
6.1.6	Title	1	
	Scale	1	
	Accuracy	1	
	Neatness	1	
	TOTAL	30	


FLOOR PLAN


SCALE 1:50

✓

ANSWER SHEET 6.2







WEST ELEVATION

SCALE 1:100

SOUTH ELEVATION

	QUESTIONS	ANSWERS	
6.2.1	What type of roof is on the building?	Gable roof	1
6.2.2	What is the slope of the roof?	30°	1
6.2.3	What is indicated by A on the drawing?	Finished Floor Level	1
6.2.4	What is indicated by B on the drawing?	Barge board	1
6.2.5	Recommend a suitable finishing for the wall of the building.	Plaster and paint/face brick	2
6.2.6	What is indicated by C on the building?	Fascia board	1
6.2.7	What does the abbreviation <i>NGL</i> stand for?	Natural ground level	1
6.2.8	Use a pencil and draw, in proportion, the position of the ridge capping on the SOUTH ELEVATION.		2
	riuge capping on the SOOTH ELEVATION.	TOTAL	10
		IOIAL	10

[40] TOTAL: 200